



REQUEST FOR QUOTATION

DATE: May 10, 2022

PURCHASE REQUEST NO.: ADMIN (GH) FUND 2022-04-68A

CANVASS NO. 69

Gentlemen:

Please quote your lowest price, taxes included, and subject to the terms and conditions that you may encounter purposely for article (s) and/or service(s) enumerated below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached here with.

Very truly yours:

EPIFANIA S. VINUYA
 BAC Chairman

ITEM NO.	QTY	UNIT	ITEM AND DESCRIPTION	UNIT PRICE	TOTAL
			Repair Works at RDEC Building (Phase-2)		
			I. General Requirements		
	1	lot	Temporary construction safety screen, platform, frame for perimeter fence, scaffolding and PPE's		
	1	lot	Hauling of debris & site clearing		
			II. Tiling Works (RM 1, RM3, RM4, 2F Hallway, Control Room, EE Room, Wall Tile Toilet of Male GF, Front Office, Service Stair GF & Main Lobby)		
	245	sq.m	Removal of existing floor & wall tiles and mortar		
	245	sq.m	Re-install non damage tiles and replace all damage tiles		
	10	sqm	III. Replacement of Dilapidated Accent Ceiling Panel & Infested KD Supply & installation of new ribbon grain plywood and frame in affected ceiling		
	15	sqm	Application of natural varnish finish on ceiling		
	1	lot	Removal of infested kd wood base board		
	450	lm	Supply, installation, varnishing & application of termite protection solution of 1" x 4" kd wood baseboard		
			IV. Replacement of Stainless Door Handle and Re-Application of Sealant on ACP Canopy		
	1	lot	Removal of existing sealant, light bulb socket & s/s door handle		
	1	lot	Repair of the ACP Canopy		
	1	set	1. Clean ACP surface with soap and water to remove grease and grime		
	1	lot	2. Polish the aluminum surface with 180-220 grit sand paper		
			3. Spray paint with lacquer spray paint (silver gray color)		
			4. Applying new sealant around the opening		
			6 inch dia. LED surface mounted downlight		
			V. Repair of Leak in Tempered Glass Window at RDEC		
	1	lot	Repair of leak in tempered glass window in main stair		
			-Removal of existing sealant		
			-Application of new silicon sealant		
			-Application of lubricant & cleaning of windows		
			VI. Others		
	20	pcs	Put stainless steel plate of all rooms toilet door @ 2nd floor		
			Size: Width of door X 600mm		
	1	lot	Repair of header of Function Hall door		
			-Increase the clearance of doors and ceiling header		
			-Paint same as the existing finish		
	1	lot	-Repair & re-alignment of Sun Canopy Louver		
			-Removing of hanging lights		

PURPOSE:

Repair works for RDEC Phase-2

Pls. submit the following eligibility documents:

- Mayor's/Business Permit
- Income Tax Return
- Notarized Omnibus Sworn Statement
- PhilGEPS Registration Number/Red Membership
- Certificate of Sole Distributorship

Note: Pls. provide also the following: contact information such as email address and mobile/landline numbers; Tax Identification Number and Bank Details

I hereby certify that I am in the position to furnish the above article(s), service(s) at the prices and in quantities as called for except as I have indicated. The articles are available in our stock for immediate delivery to the Agricultural Training Institute, Elliptical Road, Diliman, Quezon City

MODEL: _____
 DELIVERY PERIOD: _____
 WARRANTY PERIOD: _____
 PRICE VALIDITY: _____
 CANVASSED BY: _____
 DATE: _____

Signature Over printed name of proprietor/Manager
 or Authorized Representative

BAC Chairman's Office
MAY 10 2022
 B. FIL 1:30 PM

Project : PROPOSED REPAIR WORKS AT RDEC BUILDING
 Location : ATI COMPOUND, Elliptical Road, Diliman, Quezon City
 Subject : BILL OF QUANTITIES

QTY	UNIT	PARTICULARS	MATERIAL COST		LABOR COST		UNIT COST	AMOUNT
			UNIT MATERIAL COST	MATERIAL COST	UNIT LABOR COST	LABOR COST		
I. GENERAL REQUIREMENTS								
1.00	lot	Temporary construction safety screen, platform, frame for perimeter fence, scaffolding and PPE's						
1.00	lot	Hauling of debris & Site Clearing						
		sub-total I						
II. TILING WORKS (RM1, RM3, RM4, RM 20, 2F HALLWAY, CONTROL ROOM, EE ROOM GF, WALL TILE TOILET OF MALE GF, FRONT OFFICE, SERVICE STAIR GF & MAIN LOBBY)								
250.00	sq.m	Removal of existing floor tiles and mortar						
250.00	sq.m	Re-install non damage tiles and replace all damage tiles						
		sub-total II						
III. REPLACEMENT OF DILAPIDATED ACCENT CEILING PANEL & INFESTED KD WOOD IN FUNCTION HALL								
10.00	sqm	Supply & Installation of new ribbon grain plywood and frame in affected ceiling						
15.00	sqm	Application of natural varnish natural varnish finish on ceiling						
1.00	lot	Removal of infested kd wood base board						
450.00	lm	Supply, installation, varnishing & application of termite protection solution of 1" x 4" KD wood baseboard						
		sub-total III						
IV. REPLACEMENT OF STAINLESS DOOR HANDLE AND RE-APPLICATION OF SEALANT ON ACP CANOPY								
1.00	lot	Removal of existing sealant, light bulb socket & s/s door handle						
1.00	lot	Repair of the ACP Canopy 1. Clean ACP Surface with soap and water to remove grease and grime 2. Polish the aluminum surface with 180-220 grit sand paper 3. Spray paint with lacquer spray paint (silver gray color) 4. Applying new sealant around the opening						
1.00	set	6 inch dia. LED Surface mounted downlight						
		sub-total IV						
V. REPAIR OF LEAK IN TEMPERED GLASS WINDOW AT RDEC								
1.00	lot	Repair of leak in tempered glass window in main stair						
		-Removal of existing Sealant -Application of new silicon sealant - Application of lubricant & cleaning of windows						
		sub-total V						
VI. OTHERS								
20.00	pcs	Put stainless steel plate of all Rooms toilet door @ 2nd Floor Size: Width of Door X 600mm						
1.00	lot	Repair of header of Function hall Door - Increase the clearance of doors and ceiling header - Paint same as the existing finish						
1.00	lot	-Repair & Re-alignment of Sun Canopy Louver - Removing hanging lights						
		sub-total VI						
SUMMARY OF COST :								
DIRECT COST								
Material Cost :								
Labor Cost :								
INDIRECT COST								
OCM(12%)								
Profit(8%)								
Tax (5%) :								
GRAND TOTAL PROJECT COST :								