



Republic of the Philippines
Department of Agriculture

AGRICULTURAL TRAINING INSTITUTE

ATI Building, Elliptical Road, Diliman, Quezon City, Metro Manila 1100
Tel. Nos. (63-2) 8929-8541 to 49 & 8928-7397 Fax No. (63-2) 8920-9792
Email: ati_director@ati.da.gov.ph & ati_director@yahoo.com
URL: http://www.ati.da.gov.ph; www.e-extension.gov.ph

Ref. No. 2023-01-50

**SUPPLEMENTAL BID BULLETIN NO. 2 FOR THE PROCUREMENT OF BRAND-NEW
AIR-CONDITIONING UNITS (PHILGEPS Ref. No. 9378450
/ITB-ATI-CO-2022-18)**

After considering the queries, clarifications, and recommendations, the ATI-Bids and Awards Committee hereby decides to include, revise and amend the following:

- The updated specifications are as follows:

Description	Quantity
<p>Ceiling Suspended 6.0 HP Inverter Type</p> <p>230 Volts/ 3 Phase/ ~3100 Watts/ ~ 16.0 A Operation Temperature: 17 to 32 Celsius Applicable: 38 ~ 63 meter squared Low Noise Level: 51 dB (A) Airflow Volume: 1400 ~ 1900 m3/h R410A Refrigerant Maximum Piping Length: 30 mters Quiet Design, Independent Dehumidification, Auto-restart, Auto Defrosting, Timer, Sleep Mode, Indoor</p> <p>Inclusive of Labor and Installation Consumables and Restoration of affected areas of concern</p> <p>[For Mess Hall]</p>	4
<p>Floor Mounted 5 Ton Inverter Type</p> <p>230 Volts/ 3 Phase/ ~5500 Watts/ ~ 12.0 A Operation Temperature: 17 to 32 Celsius Applicable: 60 ~ 100 meter squared Low Noise Level: 51 dB (A) Airflow Volume: 1700 ~ 2400 m3/h R410A Refrigerant Maximum Piping Length: 30 mters Quiet Design, Independent Dehumidification, Auto-restart, Auto Defrosting, Timer, Sleep Mode, Indoor</p> <p>Inclusive of Labor and Installation Consumables and Restoration of affected areas of concern</p>	3

[One (1) for LeAD Library Office; One (1) for General Services & One (1) for Board Room]	
Wall Mounted, Split-Type 4 HP Inverter Type	1
<p>230 Volts/ Single Phase/ ~360 to 2,270 Watts/ ~8.2 Amps to 12.0 Amps Operation Temperature: 17 to 32 Celsius Applicable: 28 meter squared Low Noise Level: 51 dB (A) Airflow Volume: 1000 m3/h R32 Refrigerant Maximum Piping Length: 30 mters Quiet Design, Independent Dehumidification, Auto-restart, Auto Defrosting, Timer, Sleep Mode, Indoor</p> <p>Inclusive of Labor and Installation Consumables and Restoration of affected areas of concern</p> <p>[For Budget Office]</p>	

- The updated schedule of bidding activities are as follows:

Bidding Activity	Date	Time	Venue
Deadline of Submission of Bids	1/30/22	1:00 pm	ATI BAC Secretariat Office
Opening of Bids	1/30/22	1:30 pm	ATI Board Room

- **Certificate of Site Inspection** will be included in the Checklist of Requirements under Technical Envelope.
- Delivery period is up to **thirty (30)** calendar days.
- Dismantling of existing aircon is included.
- Electrical lines will be provided by the Procuring Entity.
- See attached Plan indicating the Location of Air-conditioning Unit.

All terms, conditions and instructions to bidders specified and indicated in the Bidding Documents inconsistent with this Bid Bulletin are hereby superseded and modified accordingly.

Issued this 16th day of January 2023


EDITHA S. VINUYA
 BAC Chairperson

