



Republic of the Philippines
Department of Agriculture
AGRICULTURAL TRAINING INSSTITUTE
ATI Building, Elliptical Road, Diliman, Quezon City, Metro Manila 1100
Tel. Nos. (63-2) 8929-8541 to 49 & 8928-7397 Fax No. (63-2) 8920-9792
Email: ati_director@ati.da.gov.ph & ati_director@yahoo.com
URL: http://www.ati.da.gov.ph; www.e-extension.gov.ph

PURCHASE ORDER

SUPPLIER: **TM ABAD CONSTRUCTION CORP.**
ADDRESS: Alagao, San Ildefonso, Bulacan

P.O. No.: 2024-04-80
DATE: April 4, 2024
MODE OF PROCUREMENT: NP-SMALL VALUE PROCUREMENT

TIN:

Gentlemen:

Please furnish this Office the following article(s) subject to the terms and conditions contained herein.

STOCK NO.	UNIT	DESCRIPTION	QTY	UNIT COST	TOTAL COST
	set	SUPPLY OF LABOR AND MATERIALS FOR THE VARIOUS REPAIR WORKS AT OFFICES AND PERIPHERAL OF ATI-CO MAIN BUILDING A. REPAIR OF ALUMINUM FRAME AND REPLACE THE DEFECTIVE DOOR CLOSER OF THE FOLLOWING OFFICES Office 1 - GSS Office Door size: 1.50m x 2.10m Double Leaf Aluminum Door Office 2 - HRM Office Door Size: 0.90m x 2.10m Single Leaf Aluminum Door Office 3 - Records Office Door Size: 0.90m x 2.10m Single Leaf Aluminum Door	2	14,515.20 ₱	29,030.40
	set	B. REPLACE AND INSTALL THE AUTOMATIC SLIDING DOOR MECHANISM OF TRAINING HALL AT 2ND FLOOR Specifications: Door Operation: Double sliding (Bi-parting) door Loading Weight: 2 x 120kg Door Width: 650 - 1250mm Power Supply: AC 220V 50/60Hz Power Consumption: 65 watts Opening Speed: 150-460mm/S. (adjustable) Closing Speed: 130-460mm/S. (adjustable) Open Time: 0-8 seconds (adjustable) Manual Force: <50N Temperatures: -20 + 50 degree centigrade -Aluminum Profile Dimensions: Length: 4200mm; Height: 154mm; Depth: 105mm Clear Opening Dimensions: 2000mm Width x 2460mm Height	1	11,793.60	11,793.60
	lot	Restore of the affected areas during the removal of existing mechanism and installation of new mechanism Removal of existing automatic sliding door mechanism	1	191,646.00	191,646.00
	lot	C. REPLACE AND INSTALL THE MORTISE LOCK FOR THE PPD OFFICE, DIRECTOR'S OFFICE AND ISO OFFICE S/S Mortise Lever Lock	1	5,670.00	5,670.00
	set	D. SUPPLY OF MATERIALS AND LABOR FOR REPLACING THE DEFECTIVE CCTV CAMERA AT THE LOBBY, NEAR BOARD ROOM AND AT 2ND FLOOR MAIN STAIR 2MP ColorVU Lite Fixed Turret Network Camera, High Quality Imaging, Excellent low light performance, efficient H.265+ compression technology, water and dust resistant technology, water and dust resistant technology, water and dust resistant (IP67)	5	9,922.50	49,612.50
	set	Purpose: TO REPAIR ALL THE DEFECTIVE AND DAMAGE EQUIPMENT OF THE DIFFERENT OFFICES AND PERIPHERAL OF THE MAIN BUILDING.	4	12,474.00	49,896.00
TOTAL AMOUNT IN WORDS:					₱ 375,977.70

THREE HUNDRED SEVENTY-FIVE THOUSAND NINE HUNDRED SEVENTY-SEVEN PESOS AND 70/100 ONLY

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent (1%) for everyday of delay shall be imposed.

COMFORME:

(Signature)
Signature Over Printed Name of Supplier

MAY 01, 2024
Date



Very truly yours,

(Signature)
MEMELYN K. REOTOR, MNSA, CESO III
DIRECTOR IV

FUNDS AVAILABLE:

OR/BUR No.: 02-10101-2024
03-462

GILLIAN L. SALUIB
OIC-CHIEF ACCOUNTANT

Amount: ₱ 375,977.70

